



RiverRenew

RFQ-19-079  
Information Session  
—  
Tunnel System  
Project (Design-  
Build)

June 27, 2019



RiverRenew is a program owned and implemented by Alexandria Renew Enterprises, with support from the City of Alexandria.



1800 Limerick Street | Alexandria, VA 22314





# Today's Speakers



**Liliana  
Maldonado**

AlexRenew  
Deputy  
General  
Manager



**Caitlin  
Feehan**

RiverRenew  
Program  
Manager



**Justin  
Carl**

RiverRenew  
Owner's  
Advisor



# Presentation Outline

- Introduction to Alexandria Renew Enterprises
- AlexRenew CIP and RiverRenew Contracts Update
- Overview of RiverRenew Tunnel System Components
- Tunnel System Project Procurement Process
- Next Steps
- Questions and Answers





# Introduction to Alexandria Renew Enterprises (AlexRenew)

Liliana Maldonado



# Who We Are and Who We Serve

- Special-purpose entity
- Created in 1952 by Alexandria City Council
- Led by a 5-member citizen board
- Treats an average of 35 MGD of wastewater daily to near drinking water standards
- Serves more than 300,000 customers in Alexandria and Fairfax County
- Located in Alexandria's southwest quadrant





# 2040 AlexRenew Vision



By 2040, we have effectively partnered with all watershed stakeholders to:

- Enable local citizens to **embrace the best use of water resources and establish a personal connection with local waterways.**
- Sustainably manage water as a single resource through the entire water cycle.
- **Create a healthy environment and improve our quality of life** through the exceptional reclamation of used water resources.
- Maximize use of multiple financial options to continue our fiscal stability.





# AlexRenew's Strategic Outcomes

## Operational Excellence

Continually enhance water resource and recovery procedures to provide cleaner water more efficiently.

## Public Engagement and Trust

Engage our community to help them to become informed consumers and supporters of clean water.

## Watershed Stewardship

Work collaboratively with the people we serve and other organizations in our watershed to manage and improve water resources for future generations.

## Adaptive Culture

Establish an organization-wide enthusiasm for learning, adapting, and problem solving to achieve clean water.


## Effective Financial Stewardship

Maintain a financially resilient organization that contributes to the long-term economic health of our local communities.





# AlexRenew Service Area



**Legend:**

- Service Area
- Alexandria City Limits
- - Fairfax Sewers in Alexandria
- Alexandria Sewers
- ▲ Pump Stations





RiverRenew




# AlexRenew CIP and RiverRenew Contracts Update

Liliana Maldonado

# Major AlexRenew CIP and RiverRenew Contracts as of 6/27/19

Contract	Process Air Compressor Blower Upgrades	Building J Facilities Relocation and Decommissioning (RiverRenew)	108 to 116 MGD Expansion (RiverRenew)	Wastewater Services Resident Engineering and Inspection	Other Anticipated Contracts
Description	Construction to replace existing Biological Reactor Basin blowers with High Speed Turbos	Construction to relocate building uses and building demolition	Construction to upgrade the peak raw influent capacity of the WRRF	Professional services for wastewater resident engineering and inspection	<b>Professional Services</b> <ul style="list-style-type: none"> <li>SCADA System Integration Services</li> <li>Basic Ordering Agreements</li> </ul> <b>Construction</b> <ul style="list-style-type: none"> <li>Fiber Optic Backbone Replacement</li> <li>Preliminary Primary Treatment Improvements</li> <li>Other projects as needs arise</li> </ul>
Schedule	June 2019 – December 2020	July 2019 – March 2021	August 2019 – September 2020	June 2019 – June 2020	
Contractor/Designer	ACE	Clark Construction	Bids Opened 6/25/19 – ACE Apparent Low Bidder	Hazen and Sawyer	
Cost (\$M)	\$14.4	\$19.5	\$2.6	\$3	





**Major Wastewater Projects at AlexRenew**

**Legend:**

- Process Air Compressor Blower Upgrades
- Building J Facilities Relocation and Decommissioning
- 108 to 116 MGD Expansion

City Horticultural and Natural Resources Facility

Substation

S Payne St

PEPS Upgrades

I-495

Digester Complex 20

55

C

Post Aeration Tanks

F

N

Biological Reactor Basins 44

PAC Blowers and MCC

A

L

Secondary Settling Tanks

Primary Settling Tanks 22

K

Secondary Settling Tanks

Building J

J

Filter Backwash Upgrades

22

Nutrient Management Facility (NMF)

G-2

G-1

G-3

G-5

Building G

69

Environmental Center



Limerick St

Hooffs Run

Holland Ln





# Overview of RiverRenew Tunnel System Components

Justin Carl



# Summary of Major Changes to Tunnel System Project Since November 2018 Industry Outreach Event

	Waterfront Tunnel	Hooffs Run Interceptor	Tunnel Dewatering and Wet Weather Pumping Station
<b>Associated Outfalls</b>	<ul style="list-style-type: none"> <li>• 001, 002</li> </ul>	<ul style="list-style-type: none"> <li>• 003, 004</li> </ul>	<ul style="list-style-type: none"> <li>• Relocated 004</li> </ul>
<b>Industry Outreach Approach</b> Nov 2018	<ul style="list-style-type: none"> <li>• 12-ft ID</li> <li>• Vertical alignment shown completely in Potomac Formation</li> </ul>	<ul style="list-style-type: none"> <li>• Parallel relief sewer</li> <li>• 5-ft and 6-ft diameter trenchless pipelines at AlexRenew WRRF</li> </ul>	<ul style="list-style-type: none"> <li>• <b>Tunnel Dewatering.</b> 40 MGD wet-pit submersible pumping station</li> <li>• <b>Wet Weather.</b> 130 MGD pumping station installed within an existing wet well below AlexRenew's Nutrient Management Facility</li> </ul>
<b>Current Approach</b> June 2019	<ul style="list-style-type: none"> <li>• 12-ft ID, 19-ft OD</li> <li>• Vertical alignment anticipated to be in mixed-face conditions between Alluvium and Potomac Formation</li> </ul>	<ul style="list-style-type: none"> <li>• Interceptor replacement</li> <li>• Trenchless portion removed</li> </ul>	<ul style="list-style-type: none"> <li>• Tunnel Dewatering and Wet Weather Pumping Station housed in a single shaft</li> <li>• Additional shaft for screen, clamshell, and vortex drop</li> <li>• (2) 20 MGD dry-pit submersible dewatering pumps – suction manifold</li> <li>• (4) 44 MGD wet weather pumps – suction manifold</li> </ul>


Environmental Assessment Released on June 19, 2019

# Major RiverRenew Tunnel System Components (6/19)

Component	Diameter (feet)	Length (feet)	Depth (feet)
Waterfront Tunnel	12 ID/19 OD	11,500	115-160
001 Drop Shaft	40	--	115
002 Drop Shaft	40	--	125
Mining Shaft	75	--	135
Hooffs Run Interceptor	6	2,405	10-20

## Other major components:

- Four diversion chambers
- Tunnel Dewatering (20 MGD) and Wet Weather (130 MGD) Pumping Station
- Connection into AlexRenew’s Centralized Odor Control System
- Two 3,000 cfm odor control systems (at shafts)
- Mechanical, electrical, plumbing, instrumentation, and HVAC equipment
- Superstructure at AlexRenew






# Waterfront Tunnel




# Construction Staging Areas at AlexRenew's WRRF





# Haul Routes to/from AlexRenew WRRF





# Reach 1: AlexRenew to Freedmen Cemetery (2,233-ft)



Key Map


# Reach 2: Freedmen Cemetery to Jones Point Park (2,333-ft)



Key Map



# Reach 3: Jones Point Park to Ford's Landing (2,333-ft)




Key Map

# Reach 4: Ford's Landing to Waterfront Park (2,333-ft)



Key Map


# Reach 5: Waterfront Park to Robinson Terminal North (2,281-ft)



Key Map



# Waterfront Tunnel Geologic Profile




# Outfall 001 Existing Conditions






# Outfall 001 Diversion Facility Street View






# Outfall 001 Diversion Facility

## Proposed in Environmental Assessment and City Permit Submittals





# Outfall 001 Diversion Facility Restoration



Illustrative Landscaping Plan




Rendering, looking east at Robinson Terminal North



Rendering, looking west at Robinson Terminal North



# Outfall 002 Existing Conditions





# Outfall 002 Diversion Facility

## Proposed in Environmental Assessment and City Permit Submittals





# Outfall 002 Diversion Facility Restoration



Rendering, looking southeast on South Royal Street


Illustrative Landscaping Plan



# Hoofs Run Interceptor




# Outfalls 003 and 004 Existing Conditions






# Existing Commonwealth Interceptor: Duke Street to AlexRenew WRRF






# Proposed Hooffs Run Interceptor Alignment






# Hooffs Run Interceptor Geologic Profile






# Existing Sewer Facilities Near Duke St and Daingerfield Rd






# Proposed Sewer Facilities Near Duke St and Daingerfield Rd





# Record Drawings of Commonwealth Interceptor Crossing of Jamieson Avenue

Commonwealth Interceptor  
Record Drawings - 1954




Jamieson Avenue  
Bridge Replacement - 1994



Previous  
Alignment  
(1954)


Marriot Hotel Drawings - 2000



Relocated  
Alignment






# Hooffs Run Interceptor Crossing of Jamieson Avenue







# Hooffs Run Interceptor between Jamieson Ave and AlexRenew





# Hooffs Run Interceptor Crossing of AlexRenew North Bridge






# Hooffs Run Stream Restoration

## Duke Street to Jamieson Avenue



Plan View, Duke Street to Jamieson Ave



Rendering, Looking North from Jamieson Avenue



# Hooffs Run Stream Restoration Jamieson Avenue to Eisenhower Avenue



Rendering, Looking South from Jamieson Avenue



Plan View, Jamieson Ave to Eisenhower Circle



# Hooffs Run Stream Restoration Eisenhower Avenue to AlexRenew



Plan View, Eisenhower Circle to AlexRenew




# Tunnel Dewatering and Wet Weather Pumping Station (TD/WWPS)






# Tunnel Dewatering and Wet Weather Pumping Station




# Tunnel Dewatering and Wet Weather Pumping Station – 3D View






# Tunnel Dewatering and Wet Weather Pumping Station - Top View



# Other Major Process Components Associated with the TD/WWPS

- Tunnel Debris Removal System
  - Bar screen with rake
  - Clamshell
  - Dumpster
- Reclaimed Water Flushing System
- Odor Control Blowers
  - Tie into AlexRenew's centralized scrubber system
- Pumping Station HVAC System
- Electrical System
- Bridge cranes for pump and equipment removal
- Flow Meters





# TD/WWPS Superstructure 3D Views



Rendering Looking Northeast



Rendering Looking Northwest


# Tunnel System Operational Conditions






# Plan View of Hydraulic Grade Line (HGL) Control Structure (CS)

Upper Level Plan (-9.0 ft)




Lower Level Plan (-20.0 ft)




# Dry Weather Flow

## Plan View



## Sectional View




**Notes:**  
**1** All flow contained in the sanitary interceptor system




# Typical Wet Weather Flow: 40-50 storms/year

## Plan View



## Sectional View




### Notes:


- 1** All 003/4 flows conveyed directly to WRRF Headworks
- 2** TD/WWPS pumps 001/2 flows to HGL CS to maximize flow to plant (i.e. pumps up to 20 mgd or until WRRF reaches 116 mgd)

# Larger Wet Weather Flows: 6-8 storms/year

## Plan View



## Sectional View




### Notes:

- 1** Maximize flow to WRRF up to 116 mgd
- 2** 003/4 flows stay in sanitary sewer until WRRF at 116 mgd, then 003/4 flows discharge over HGL CS weir
- 3** Gravity flow from 003/4 through flap gate to TDPS
- 4** Flows from 003/4 combine with flows from 001/2




# Wet Weather Treatment Activation: 1-4 storms/year

## Plan View



## Sectional View




### Notes:


- 1** WWPS is operating and pumping flows at 40 mgd
- 2** 40 mgd of flow is sent to Wet Weather Treatment (WWT)

# Transfer Flow to Outfall 001: 1-2 storms/year

## Plan View



## Sectional View




### Notes:

- 1** WWPS is operating and pumping flows at 80 mgd
- 2** 40 mgd of flow is sent to WWT
- 3** 40 mgd of flow sent to Outfall 001




# Discharge from Outfall 004: Less than 1 storm/year

## Plan View



## Sectional View



### Notes:

- 1** WWPS is operating and pumping flows at 130 mgd
- 2** 40 mgd of flow is sent to WWT
- 3** 40 mgd of flow sent to Outfall 001
- 4** Remaining flow (50 mgd) sent to Relocated Outfall 004



RiverRenew




# Tunnel System Project Procurement Process

Caitlin Feehan



# Design-Build Process for the Tunnel System Project




# Anticipated Responsibilities for Tunnel System Design-Build Project (not a complete scope of work)

Project Element	AlexRenew	Design-Builder
Open Channel Hydraulics	✓	
Tunnel Dewatering and Wet Weather Pumping Station	Performing physical modeling	✓
Permanent Structures		✓
Mechanical, Electrical, and Instrumentation		✓
Support of Excavation		✓
Tunnel Excavation		✓
Ground Improvement		✓
Geotechnical Instrumentation		✓
Protection of Structures		✓
Utility Relocations		✓
Maintenance of Traffic		✓
Civil Design and Landscaping		✓
Stakeholder and Community Engagement	✓	
Major Federal and State Permits	✓	
Property Easements and Agreements	✓	
City of Alexandria Development Special Use Permit	✓	D-B will submit Final Site Plan
City of Alexandria Construction Permits		✓



# Anticipated Technical/Management and Price Weighting for Second Step of Procurement Process



Proposal Payment provided to unsuccessful Shortlisted Teams that submit responsive proposals (\$300 - \$500k)

# Anticipated Design-Build Contract Provisions for the Tunnel System Project

Schedule Milestones and Liquidated Damages	Escrow Bid Documents	Mobilization Payment Items
Mutual Waivers of Consequential Damages	Design-Builder Provided Insurance	Facilitated Partnering
Dispute Resolution Board	Allowance Payment Items	Retainage at 5 percent
Differing Site Conditions and the use of Geotechnical and Environmental Baseline Reports	VCWRLF and WIFIA requirements for M/WBE, Davis-Bacon, and American Iron and Steel	Alternative Technical Concept Process



## Experience with the Following is Important to AlexRenew:

- Team members working together.
- Design-Build.
- Tunnel and shaft construction of similar diameter and depth in similar ground conditions.
- Pumping stations and wet weather facilities of similar function, capacity, and depth.
- Pipelines installed by open-cut methods with connections to live sewers.
- Constructing similar facilities and mitigating community impacts in congested residential and commercial urban environments.

# Tunnel System Project Key Personnel

40%

Key Personnel	Project Manager	Construction Manager	Design Manager	Design Coordinator	Key Personnel Identified by Design-Builder		
					1	2	3
Description	Responsible for managing all aspects of the Project.	Responsible for the implementation of designs associated with all project components.	Responsible for managing design activities and ensuring coordination across all design disciplines.	Responsible for coordinating design and construction activities to ensure approaches are compatible and schedule is maintained.	To be identified by Design-Builder	To be identified by Design-Builder	To be identified by Design-Builder
Certifications			Virginia Licensed PE				

AlexRenew does not view a **Permit Coordinator** or a **Community Outreach Specialist** as Key Personnel



# Related Project Experience

40%

Construction Reference Projects					Design Reference Projects		
1 - Tunnel	2 - Tunnel	3 - Pumping Station	4 - Pumping Station	5 - Open-cut	1	2	3
Tunnel and shaft construction of similar diameter and depth in similar ground conditions	Tunnel and shaft construction of similar diameter and depth in similar ground conditions	Pumping stations and wet weather facilities of similar function, capacity, and depth	Pumping stations and wet weather facilities of similar function, capacity, and depth	Pipelines installed by open-cut methods with connections to live sewers	Tunnel, Pumping Station, or Open-cut	Tunnel, Pumping Station, or Open-cut	Tunnel, Pumping Station, or Open-cut

Lead Contractor(s) and Lead Designer(s)

# 3


## Unique Risks

- Narrative
- Impact
- Mitigation
- Role
- Responsible Party



# Safety Program and Record

10%



# Other Forms and Required Documents

## Virginia SCC Registration Form

## Surety Letter

- Performance and Payment Bond value of \$300 million
- Rating categorization

## Audited Financial Reports and Net Worth

- 3 most recent fiscal years
- Prepared in accordance with U.S. GAAP
- Identification of contract default, criminal conviction, debarment for Lead Contractor(s) and Lead Designer(s)
- Demonstrated net worth of at least \$30 million



# AlexRenew will use the Virginia Clean Water Revolving Loan Fund (VCWRLF) and Water Infrastructure Finance and Innovation Act (WIFIA) to Assist with Funding for RiverRenew

- Equal Employment Opportunity Compliance
- Minority Business Enterprise (MBE)/ Women Business Enterprise (WBE) Fair Share Goals
- Davis-Bacon Compliance
- American Iron and Steel

## VCWRLF M/WBE Goals in current AlexRenew construction contracts (may change by bid time)

	MBE%	WBE%
Construction	7.4	4.8
Equipment	5.0	3.2
Services	7.7	3.6
Supplies	1.6	2.5

*Contractors must demonstrate a "good faith effort" in the solicitation and utilization of MBEs/WBEs during the bid process:*

- *Public notice and/or direct solicitations must be undertaken*
- *Evidence of these efforts and anticipated MBE/WBE utilization must be presented and must demonstrate a "good faith effort"*



RiverRenew



# Next Steps and Questions and Answers

Liliana Maldonado



# Next Steps

Download the RFQ Information Session Presentation: [alexrenew.com/riverrenew-tunnel-system-project-design-build](https://alexrenew.com/riverrenew-tunnel-system-project-design-build)

➔ Only email [tunnelsystem@alexrenew.com](mailto:tunnelsystem@alexrenew.com) for questions related to this RFQ

## RFQ-19-079: Tunnel System Project (Design-Build)

- **August 1.** Last Day for Questions
- **August 13.** Last Date for Addenda
- **August 20.** SOQs Due
- **October 15.** Notify Shortlisted Teams

## Tunnel System Resident Engineering and Inspection (RE&I) Contract

- **November 2019.** Issue Tunnel System RE&I Request for Proposals




# AlexRenew Water Resource Recovery Facility Site Tour

Justin Carl



# AlexRenew WRRF Site Tour Map



★	Environmental Center
1	5MW Temporary Power Drop
2	North Bridge Hooffs Run Interceptor
3	Building G Construction Staging Area
4	Tunnel Dewatering Pumping Station Construction Staging Area
5	Building L Centralized Odor Scrubber
6	Trailer Complex
7	Perimeter Road Construction Staging Area
8	South Bridge Hooffs Run Junction Chamber

# Questions and Answers

